

Norms

-BUILDING LOAD-BEARING AND PARTITION WALLS-



www.polet.rs

Norms – Building load-bearing walls -THERMO PROGRAM-

TB 20	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	55	0,10	2,10	0,75

TB 25	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	44	0,10	2,00	0,75

TB 30	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	56	0,15	2,10	0,75

TB 38	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	44	0,15	2,00	0,6

TB 25/30	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	56	0,15	2,10	0,75

Notes:

QWF – Qualified workforce

SSWF – Semi-skilled workforce

**Norms – Building load-bearing walls
-THERMO OPTIM PROGRAM-**

TB 20 Optim	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	55	0,10	2,10	0,75

TB 25 Optim	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	44	0,10	2,00	0,75

TB 30 Optim	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	56	0,15	2,10	0,75

Notes:

QWF – Qualified workforce

SSWF – Semi-skilled workforce

**Norms – Building load-bearing walls
-CLASSIC PROGRAM-**

Giter 25	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	110	0,16	3,20	0,9

Giter 29	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	95,5	0,16	3,00	0,8

Giter 25 Optim	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	110	0,16	3,20	0,9

Fert 14	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	10	0,1	0,40	1,6

Fert 16	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	10	0,16	0,40	1,6

Notes:

QWF – Qualified workforce

SSWF – Semi-skilled workforce

Norms – Building partition walls -PARTITION PROGRAM-

Partition block 10/23,8/38	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	10,7	0,01	0,60	0,3

Partition block 12/23,8/38	MATERIAL		WORK	
	Brick pcs/m ³	Mortar m ³ /m ³	QWF hour/m ³	SSWF hour/m ³
	10,7	0,01	0,60	0,3

Notes:

QWF – Qualified workforce

SSWF – Semi-skilled workforce